Make My Interiors
the joy of best living

Address: Office No. 201, Reelicon capital, Pune-Satara Road,Walvekar nagar, Pune

Client's Details		Company Details	
Name:	MR SATISH PAWAR	Contact No. :	9881951312/9834375579/8888859349
Project Address:	KESHAV NAGAR	Email:	info@makemyinteriors.in
Phone No.		Website:	makemyinteriors.in
Property		GSTIN:	27AANCM6061F1ZA

Item	Specifications	Size			Rate	Amount
		Width	Height	Total sq. ft		
ENTERANCE						
SHOE RACK	IN 18 MM PLY AND 1 MM LAMINATE SHOE RACK WITH 2 DRAWERS	3	3.6	10.8	1300	14040
SITTING NEAR SHOE RACK	IN PLY AND LAMINATE WITH STORAGE BELOW	2	1.8	3.6	1300	4680
SAFTY DOOR	IN 25 MM BLOCK BOARD AND 1 MM LAMINATE WITH MS POWDER CATED JALI WITH DESIGNER HANDLE , EUROPA LATCH LOCK	3.6	7.2	25.92	1200	31104
PANALLING AROUND SAFTY DOOR	IN 12 MM PLY AND LAMINATE AS PER DESIGN	6	9	54	600	32400
FOYER AREA						
CONSOLE UNIT	IN 18 MM PLY AND 1 MM LAMINATE SHOE RACK WITH 2 DRAWERS	5	3.6	18	1300	23400
PANALLING ABOVE CONSOLE UNIT	IN 12 MM PLY AND LAMINATE WITH WALLPAPER AND MDF MOLDING PANALLING	5	6	30	600	18000
LIVING ROOM						
TV UNIT	IN 18 MM PLY AND 1 MM LMINATE WITH LIUVERS AND SHOWCASE BOX (VERY MINIMAL)	8	8.9	71.2	1100	78320
MANDIR BESIDES TV UNIT	IN 18 MM PLY AND 1 MM LAMINATE WITH ACRYLIC JALI AND ACRYLIC DESIGN BEHIND(DOORS AND SITTING NOT INCLUDED)	2.6	7.6	19.76	1600	31616
SOFA	IN PINE WOOD FRAME AND BRANDED FAABRIC AND 45 DENSITY FOAM (CUSTOM COUTCH BRAND)	5 SEATER				60000

SOFA BACK WALL	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER	10	9	90	400	36000
DINING AREA						
DINING TABLE(4 SEATER)	DINING ATBLE MADE BY CARPENTER WITH LAMINATED TOP AND READYMADE CHAIRS	4	4			56000
DINING BACK WALL	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER	5	9	45	500	22500
KITCHEN						
WALL CABINETS	IN 18 MM BWP PLY AND 1 MM INTERNAL LAMINATES AND 1.5 MM ACRYLIC FACTORY FINISHED DOORS	15	2.6	39	1600	62400
LOFT (L SHAPE)	IN 18 MM BWP PLY AND 1 MM INTERNAL LAMINATES AND 1.5 MM ACRYLIC FACTORY FINISHED DOORS	20	2	40	1600	64000
MASTER BEDROOM						
BED	IN 18 MM PLY AND 1 MM LAMINATE WITH HYDRAULIC TOP WITH STORAGE	6	6.6	39.6	1100	43560
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	6	2.6	15.6	600	9360
BED BACK PANALLING	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER DESIGN AS PER SELECTION (PRICE CAN VARY)	9	8	72	500	36000
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH OPENABLE OR SLIDING DOORS WITH HANGER RODS INSIDE , 4 DRAWERS INSIDE	7	9	63	1600	100800
STUDY TABLE WITH OVERHEAD STORAGE	IN 18 MM PLY AND 1 MM LAMINATE WITH WRITING BOARD	3	7	21	1300	27300
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14	1600	22400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS	2	1.8			6000
MASTER BEDROOM BATHROOM						

GLASS PARTITION	10 MM TOUGHNED GLASS PARTITION	2.6	7	18.2	600	10920
PVC CEILING	PVC CEILING IN BATHROOM	8	4.6	36.8	160	5888
STORAGE UNDER SINK	IN PVC PLY AND LAMINATE	2	2	4	1500	6000
MIRROR	MIRROR WITH ALLUMINIUM FRAME WITH LED LIGHT	2.6	2			5000
KIDS BEDROOM						
BED	18 MM PLY AND 1 MM LAMINATE BED WITH HYDROLIC STORAGE	5	6.6	33	1100	36300
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	5	2.6	13	600	7800
BED BACK PANALLING	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER DESIGN AS PER SELECTION (PRICE CAN VARY)	9	8	72	500	36000
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH OPENABLE OR SLIDING DOORS WITH HANGER RODS INSIDE , 4 DRAWERS INSIDE	6	9	54	1600	86400
STUDY TABLE WITH OVERHEAD STORAGE	IN 18 MM PLY AND 1 MM LAMINATE WITH WRITING BOARD	3	7	21	1300	27300
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14	1600	22400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS	2	1.8			6000
GUEST BEDROOM						
SOFA CUM BED	FOLDABLE SOFA CUM BED IN PLY AND LAMINATE	5	6.6	33	1200	39600
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH SLIDING DOORS OR OPENABLLE DOORS WITH 4 DRAWERS AND HANGER RODS	6	9	54	1600	86400
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	5	2.6	13	600	7800
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14	1600	22400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS	2	1.8			6000

COMMON BATHROOM						
GLASS PARTITION	10 MM TOUGHNED GLASS PARTITION	2.6	7	18.2	600	10920
PVC CEILING	PVC CEILING IN BATHROOM	8	4.6	36.8	160	5888
STORAGE UNDER SINK	IN PVC PLY AND LAMINATE	2	2	4	1500	6000
MIRROR	MIRROR WITH ALLUMINIUM FRAME WITH LED LIGHT	2.6	2			5000
OTHER ITEMS						
FALSE CEILING	POP IN GYPROC GYPSUM SHEET WITH PREMIUM QUALITY CAHNNEL	660	1.7	1122	80	89760
INVERTER BOX	MS GRILL AT BASE WITH PLY COVERING AND 1 MM LAMINATE FINISHED WITH JALI FOR VENTILATION	4	2.3	9.2	1400	12880
INVISIBLE GRILL	2 MM THICKNESS WITH 2.5 INCH GAP INVISIBLE GRILL	95 SQFT		95	140	13300
ELECTRIC POINT SHIFTNIG	ELECTRIC POINTS SHIFTING FOR FALSE CEILING AND FURNITURE (POINTS CAN VARY AS PER REQUIRMENT)	80			800	64000
LIGHTS,LEDS, CHOKE, SPOT LIGHTS, PROFILE LIGHTS	LIGHTS COST LIKE SPOT LIGHT, PROFILE LIHGHTS, PANAL LIGHTS OF BRAND ORIENT OR BAJAJ, LED					45000
SWITCH SOCKET FOR EXTRA LIGHTS POINT	EXTRA SWITCH AND SOCKETS FOR EXTRA LIGHT POINTS EXCEPT EXISTING SWITCH SOCKETS					14000
DEBRIES TRANSPORT AND DUMPING						12000
DEEP CLEANING						8000
PAINT	ASIAN PAINT LUSTER WITH 2 COAT PUTTI, 2 COAT PRIMER AND 2 COAT PAINT					85000
		TOTAL				**1563836**
	DESIGNER FEES		**6%**			**93830**
	GRAND TOTAL					**1657666**

Specifications of Materials :All material used by us is ISI trademarked

Ply wood /Blockboard - 18mm alternate gurjan plywood for furniture work, 18mm BWR plywood for all kitchen work

Laminate - 1mm thickness laminate to be used for furniture. Standard laminate rate for outside laminates of Rs.1800 to 2200 per sheet has been considered (1 mm laminate considered to all furniture)premium fluted, smooth finish ,stone finish, self design laminates will be used

Laminates inside are white / off white/ fabric finish of 1 mm thickness			
Hardware and Hinges -ONYX(soft close) for hinges			
Europa for wardrobe locks			
The interior work included edge binding to give better finish			
Additional accessories as well as light fittings have not been included in the quote			
All hinges are soft closure for kitchen , living , dinning , entry passage , others unit like overhead loft storage.ONYX (NON SOFT CLOSE) drawers channals will be used			
PREMIUM EMULSION paint of asian paint to be used for all walls AND premium emulsion for CEILING			
PAYMENT SLAB			
ADVANCE	This is for design phase		50,000
1ST SLAB	In this slab all pop work will be finish, plywood,internal laminate , fevicol and basic hardware will be deliverd on site and pasting of laminate will be done	30%	
2ND SLAB	in this slab all carcus work will be finished, and hardware like hinges, chanells will be deliverd on site, civil work will be done	25%	
3 RD SLAB	In this slab all kitchen material order will be places, all color laminate, bed fittings, warddrobe fittings will be deliverd on site and laminate work will start	25%	
4TH SLAB	In this slab all color laminate work finish, all pending works	15%	
5TH SLAB	This slab is after handover, design cost will minimise from this slab	5%	
	TOTAL	100%	