Interiors by Pooja

Turning spaces into stories you'll love

Date: 2026-10-11
Grand Total: Rs. 16,57,666

Client's Details		Company Details	
Name:	Satish Kumar	**Contact:**	8483846288
Project Address:	KESHAV NAGAR	**Office Address:**	Que914, C-1802, Keshav Nagar, Mundhwa, Pune, Maharashtra 411036

Foyer Area

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
SHOE RACK	IN 18 MM PLY AND 1 MM LAMINATE SHOE RACK WITH 2 DRAWERS	3	3.6	10.8	1300	Rs. 14,040
SITTING NEAR SHOE RACK	IN PLY AND LAMINATE WITH STORAGE BELOW	2	1.8	3.6	1300	Rs. 4,680
SAFTY DOOR	IN 25 MM BLOCK BOARD AND 1 MM LAMINATE WITH MS POWDER CATED JALI WITH DESIGNER HANDLE, EUROPA LATCH LOCK	3.6	7.2	25.92	1200	Rs. 31,104
PANALLING AROUND SAFTY DOOR	IN 12 MM PLY AND LAMINATE AS PER DESIGN	6	9	54.0	600	Rs. 32,400
					Section Total	**Rs. 82,224**

Living Room

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
CONSOLE UNIT	IN 18 MM PLY AND 1 MM LAMINATE SHOE RACK WITH 2 DRAWERS	5	3.6	18.0	1300	Rs. 23,400
PANALLING ABOVE CONSOLE UNIT	IN 12 MM PLY AND LAMINATE WITH WALLPAPER AND MDF MOLDING PANALLING	5	6	30.0	600	Rs. 18,000
TV UNIT	IN 18 MM PLY AND 1 MM LMINATE WITH LIUVERS AND SHOWCASE BOX (VERY MINIMAL)	8	8.9	71.2	1100	Rs. 78,320
MANDIR BESIDES TV UNIT	IN 18 MM PLY AND 1 MM LAMINATE WITH ACRYLIC JALI AND ACRYLIC DESIGN BEHIND(DOORS AND SITTING NOT INCLUDED)	2.6	7.6	19.76	1600	Rs. 31,616
SOFA	IN PINE WOOD FRAME AND BRANDED FAABRIC AND 45 DENSITY FOAM (CUSTOM COUTCH BRAND) 5 SEATER					Rs. 60,000
SOFA BACK WALL	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER	10	9	90.0	400	Rs. 36,000
					Section Total	**Rs. 2,47,336**

Dining Area

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
DINING TABLE(4 SEATER)	DINING ATBLE MADE BY CARPENTER WITH LAMINATED TOP AND READYMADE CHAIRS					Rs. 56,000
DINING BACK WALL	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER	5	9	45.0	500	Rs. 22,500
					Section Total	**Rs. 78,500**

Kitchen

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
WALL CABINETS	IN 18 MM BWP PLY AND 1 MM INTERNAL LAMINATES AND 1.5 MM ACRYLIC FACTORY FINISHED DOORS	15	2.6	39.0	1600	Rs. 62,400
LOFT (L SHAPE)	IN 18 MM BWP PLY AND 1 MM INTERNAL LAMINATES AND 1.5 MM ACRYLIC FACTORY FINISHED DOORS	20	2	40.0	1600	Rs. 64,000
					Section Total	**Rs. 1,26,400**

Master Bedroom

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
BED	IN 18 MM PLY AND 1 MM LAMINATE WITH HYDRAULIC TOP WITH STORAGE	6	6.6	39.6	1100	Rs. 43,560
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	6	2.6	15.6	600	Rs. 9,360
BED BACK PANALLING	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER DESIGN AS PER SELECTION (PRICE CAN VARY)	9	8	72.0	500	Rs. 36,000
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH OPENABLE OR SLIDING DOORS WITH HANGER RODS INSIDE, 4 DRAWERS INSIDE	7	9	63.0	1600	Rs. 1,00,800
STUDY TABLE WITH OVERHEAD STORAGE	IN 18 MM PLY AND 1 MM LAMINATE WITH WRITING BOARD	3	7	21.0	1300	Rs. 27,300
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14.0	1600	Rs. 22,400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS					Rs. 6,000
					Section Total	**Rs. 2,45,420**

Master Bedroom Bathroom

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
GLASS PARTITION	10 MM TOUGHNED GLASS PARTITION	2.6	7	18.2	600	Rs. 10,920
PVC CEILING	PVC CEILING IN BATHROOM	8	4.6	36.8	160	Rs. 5,888
STORAGE UNDER SINK	IN PVC PLY AND LAMINATE	2	2	4.0	1500	Rs. 6,000
MIRROR	MIRROR WITH ALLUMINIUM FRAME WITH LED LIGHT					Rs. 5,000
					Section Total	**Rs. 27,808**

Guest Bedroom

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
BED	18 MM PLY AND 1 MM LAMINATE BED WITH HYDROLIC STORAGE	5	6.6	33.0	1100	Rs. 36,300
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	5	2.6	13.0	600	Rs. 7,800
BED BACK PANALLING	IN PLY AND LAMINATE WITH MDF MOLDINGS AND WALLPAPER DESIGN AS PER SELECTION (PRICE CAN VARY)	9	8	72.0	500	Rs. 36,000
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH OPENABLE OR SLIDING DOORS WITH HANGER RODS INSIDE, 4 DRAWERS INSIDE	6	9	54.0	1600	Rs. 86,400
STUDY TABLE WITH OVERHEAD STORAGE	IN 18 MM PLY AND 1 MM LAMINATE WITH WRITING BOARD	3	7	21.0	1300	Rs. 27,300
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14.0	1600	Rs. 22,400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS					Rs. 6,000
					Section Total	**Rs. 2,22,200**

Kids Bedroom

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
SOFA CUM BED	FOLDABLE SOFA CUM BED IN PLY AND LAMINATE	5	6.6	33.0	1200	Rs. 39,600
WARDROBE	IN 18 MM PLY AND 1 MM LAMINATE WITH SLIDING DOORS OR OPENABLLE DOORS WITH 4 DRAWERS AND HANGER RODS	6	9	54.0	1600	Rs. 86,400
BED BACK CUSHION	IN FOAM AND FABRIC CUSHION IN SELECTED DESIGN	5	2.6	13.0	600	Rs. 7,800
DRESSING TABLE	IN PLYN AND LAMINATE WITH STORAGE AND FULL SIZE MIRROR AND 2 DRAWERS	2	7	14.0	1600	Rs. 22,400
SIDE TABLE	IN PLY AND LAMINATE WITH 2 DRAWERS					Rs. 6,000
					Section Total	**Rs. 1,62,200**

Common Bathroom

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
GLASS PARTITION	10 MM TOUGHNED GLASS PARTITION	2.6	7	18.2	600	Rs. 10,920
PVC CEILING	PVC CEILING IN BATHROOM	8	4.6	36.8	160	Rs. 5,888
STORAGE UNDER SINK	IN PVC PLY AND LAMINATE	2	2	4.0	1500	Rs. 6,000
MIRROR	MIRROR WITH ALLUMINIUM FRAME WITH LED LIGHT					Rs. 5,000
					Section Total	**Rs. 27,808**

Other Items

Item	Specifications	Width	Height	Total sq. ft.	Rate	Amount
FALSE CEILING	POP IN GYPROC GYPSUM SHEET WITH PREMIUM QUALITY CAHNNEL			1122	80	Rs. 89,760
INVERTER BOX	MS GRILL AT BASE WITH PLY COVERING AND 1 MM LAMINATE FINISHED WITH JALI FOR VENTILATION	4	2.3	9.2	1400	Rs. 12,880
INVISIBLE GRILL	2 MM THICKNESS WITH 2.5 INCH GAP INVISIBLE GRILL 95 SQFT			95	140	Rs. 13,300
ELECTRIC POINT SHIFTNIG	ELECTRIC POINTS SHIFTING FOR FALSE CEILING AND FURNITURE (POINTS CAN VARY AS PER REQUIREMENT)			80	800	Rs. 64,000
LIGHTS,LEDS, CHOKE, SPOT LIGHTS, PROFILE LIGHTS	LIGHTS COST LIKE SPOT LIGHT, PROFILE LIHGHTS, PANAL LIGHTS OF BRAND ORIENT OR BAJAJ, LED					Rs. 45,000
SWITCH SOCKET FOR EXTRA LIGHTS POINT	EXTRA SWITCH AND SOCKETS FOR EXTRA LIGHT POINTS EXCEPT EXISTING SWITCH SOCKETS					Rs. 14,000
DEBRIES TRANSPORT AND DUMPING						Rs. 12,000
DEEP CLEANING						Rs. 8,000
PAINT	ASIAN PAINT LUSTER WITH 2 COAT PUTTI, 2 COAT PRIMER AND 2 COAT PAINT					Rs. 85,000
					Section Total	**Rs. 3,43,940**

Work Total	**Rs. 15,63,836**
Designer Fees 6%	**Rs. 93,830**
Grand Total	**Rs. 16,57,666**

Specifications of Materials

All material used by us is ISI trademarked.
Ply wood /Blockboard - 18mm alternate gurjan plywood for furniture work, 18mm BWR plywood for all kitchen work.
Laminate - 1mm thickness laminate to be used for furniture. Standard laminate rate for outside laminates of Rs.1800 to 2200 per sheet has been considered (1 mm laminate considered to all furniture) premium fluted, smooth finish, stone finish, self design laminates will be used.
Additional accessories as well as light fittings have not been included in the quote.
All hinges are soft closure for kitchen, living, dinning, entry passage, others unit like overhead loft storage. ONYX (NON SOFT CLOSE) drawers channals will be used.
PREMIUM EMULSION paint of asian paint to be used for all walls AND premium emulsion for CEILING.
Hardware and Hinges - ONYX(soft close) for hinges.
Europa for wardrobe locks.
The interior work included edge binding to give better finish.
Laminates inside are white / off white/ fabric finish of 1 mm thickness.

Payment Slab	Details	Value
ADVANCE	This is for design phase	50,000
1ST SLAB	In this slab all pop work will be finish, plywood, internal laminate, fevicol and basic hardware will be deliverd on site and pasting of laminate will be done	30%
2ND SLAB	In this slab all carcus work will be finished, and hardware like hinges, chanells will be deliverd on site, civil work will be done	25%
3 RD SLAB	In this slab all kitchen material order will be places, all color laminate, bed fittings, warddrobe fittings will be deliverd on site and laminate work will start	25%
4TH SLAB	In this slab all color laminate work finish, all pending works	15%
5TH SLAB	This slab is after handover, design cost will minimise from this slab	5%
TOTAL		100%